



NOTES:

1. EXPANSION JOINTS: AT CURB RETURNS, ADJACENT TO STRUCTURES AND 45' (6' WIDE SIDEWALKS) OR 50' (5' WIDE SIDEWALKS).
2. TOOLED JOINTS WITH 1/4" GROOVES AND 1/4" RADIUS.
3. MEDIUM BROOM FINISH. FINISH QUALITY AND WORKMANSHIP SHALL BE PER STAFF-PROVIDED REFERENCE AREA AND PER STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION. THE FIELD ENGINEERING INSPECTOR SHALL HAVE THE FINAL DETERMINATION OF APPROVAL.
4. CONCRETE SHALL BE 520-C-2500 PER STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION AND SHALL BE 4" THICK.
5. CURB JOINTS ARE TO BE ALIGNED WITH SIDEWALK JOINTS. (TBD)



APPROVED BY: <i>mch</i>		DATE: 03/21/16	<b>CITY OF MONTCLAIR PUBLIC WORKS DEPARTMENT</b>	
REVISION	DESCRIPTION	DATE		
			STANDARD DWG. SP-1	